



State Environment Impact Assessment Authority, M.P.
(Government of India, Ministry of Environment, Forest & Climate Change)

Environmental Planning Coordination Organization (EPCO)
Paryavaran Parisar, E-5. Arera Colony
Bhopal-4620 16

visit us <http://www.mpseiaa.nic.in>
Tel: 0755-2466970, 2466859

Fax : 0755-2462136

No: 2831 /SEIAA/2019

Date: 28.3.19

To,
Executive Engineer,
Water Resource Division,
Near Harsud Naka, Civil Line, Khandwa,
Dist. Khandwa, MP – 450001

Sub:- Case No. 5546/2017: Prior Environment Clearance for proposed Bham Medium Irrigation Project at Bham (Rajgarh), Dist. Khandwa, MP Gross Command Area (GCA): 9000 ha; Culturable Command Area (CCA): 6100 ha Catchment area – 193.45 ha by Executive Engineer, Water Resource Division, Near Harsud Naka, Civil Line, Khandwa, Dist. Khandwa, MP - 450001 Engineer-in-Chief, Water Resources Department, Jal Sansadhan Bhawan, Tulsi Nagar, Bhopal E-mail: ee wrdkhandwa@yahoo.com encwr bpl-mp@nic.in mob no. – 9300683856 Env. Consultant- Voyants Solutions Pvt. Ltd. Gurgaon

Ref: Your application dtd. 28.03.17 received in SEIAA office on 18.04.2017

With reference to the above, the proposal has been appraised as per prescribed procedure & provisions under the EIA notification issued by the Ministry of Environment & Forests vide S.O. 1533 (E), dated 14th September 2006 and its amendments, on the basis of the mandatory documents enclosed with the application viz., Form I, pre-feasibility report, ToR, EMP Report, ppt. and additional clarifications furnished in response to observations by the State Expert Appraisal Committee (SEAC) and State Environment Impact Assessment Authority (SEIAA) constituted by the competent Authority.

- i. The project is located near village Rajgarh on Bham River which is a tributary of Chhota Tawa draining to Indira Sagar Reservoir on the river Narmada from left. The project comes under Khandwa Tehsil of Khandwa District. The Dam site is at a distance of 0.12 km. on east of Rajgarh village.
- ii. The project has been conceived with a view to impound 32.34 MCM of monsoon discharge of the river and harness it for providing irrigation facility to 6100 ha during Rabi with 100 % annual irrigation intensity, besides earmarking 0.361 MCM for drinking water. With piped canal, micro irrigation by sprinkler system the project efficiency can be achieved up to 84% against 45% for open unlined canal system. The project shall encompass the following components:-
 - a. 3108 m long composite dam comprising of maximum height of 16.50 m homogeneous earthen dam;
 - b. 148 m wide spillway;
 - c. 7.50 km and 5.50 km long two rising main
 - d. Distribution net work of 10 minors (44.50kms).

- iii. The project pertains to Item No. 1(c) category 'B' of the EIA Notification 2006 schedule and in terms of Notification dated, 25th June, 2014, as the CCA of the project is less than 10000 ha.
- iv. The project has a command area of 6100 ha, therefore as per EIA notification of September 2006 and a recent amendment (August 14, 2018), it is a Category B2 project (Medium irrigation project having CCA > 2000 ha and < 10000 ha)". And Being a B2 Category project, it does not require an EIA report and is exempt from Public Hearing; it require submission of EMP only However, Scoping Clearance of the project was taken as Category B1 (prior to August 2018 amendment).
- v. There is no wildlife sanctuary, National park (DFO letter dtd. 20.03.17) or interstate boundaries (PWD letter dtd. 16.03.17) within 10 km of the project area hence general conditions are not attracted.
- vi. The predominant land use class is agriculture land (76.63%) followed by dense forest (12.63%), Barren land (5.54%), open forest (0.79%), water body (1.10%) and settlement (3.30%).
- vii. For execution of the project 857.66 ha land shall be required of which the apportionment between private, government & forest land shall be 617.40 ha, 91.51 ha and 148.75 ha respectively.
- viii. Due to project there shall be loss of 617.40 ha agricultural land and consequently loss of production from the land. The project affected families shall be adequately compensated for land loss and cost of land to be acquired as per provision under RFCT_LARR 2013. Besides this, 148.75 ha of forest land and 91.51 ha. Revenue shall be brought under submergence along with 5833 trees of mixed and teak species. For compensating, loss of forest land the District Collector Khandwa vide letter No.50/A-59/2016, passed order for executing transfer of 148.75 ha revenue land falling in Surgaon Nipani Village (khasra Nos.12, 20, 31, 32, 33, 34, 35, 50, 51 and 52) to the Divisional Forest Officer, Khandwa for raising Compensatory Afforestation in lieu of equivalent forest land purposed to be diverted for the project. The revenue land under submergence is barren land. PP has obtained stage-1 forest clearance issued vide letter no. F. No. 8-34/2018-FC dated 31/10/2018.
- ix. The State Government of Madhya Pradesh vide S.N.22 (A) 349/51/18/SPS/31/1311, dated 27.7.2018 has sanctioned a special package for submergence affected area in case of Bham Medium Irrigation Project. As per paragraph A(i) G.O. dated 27.7.2018.the purchase/ acquiring cost per hectare of land shall be paid Lump sum @ Rs 10 lakh/ha.
- x. Solid waste generated from temporary and permanent colonies in construction as well as operation phase requires special management to disposed of as warranted under the new Solid Wastes Management Rules, 2016.
- xi. The disposal of untreated sewage can lead to water pollution, resulting in increase in coliforms and other various pathogens, which can lead to incidence of water borne diseases. For avoiding this situation provision of STP has been made in the EMP. The sewage waste shall be disposed after treatment through STP.
- xii. To avoid the dust generation during the drilling operations, wet drilling method will be practiced or wet drill machine will be used. Dust mask will also be provided to the workers. Proper regular maintenance of machineries will be

- done. Speed of the vehicles will be kept within the prescribed limits. Trucks/ dumpers will not be over loaded. At the feeding points stone crusher air mist spray shall be carried out and hooded conveyer belts shall be used.
- xiii. Under the Catchment Area Plan it is proposed to addresses issues such as prevention of gully erosion, enhancing the forest cover for increasing soil holding capacity; and arresting total sediment flow in the reservoir and flowing waters. 727 ha have been proposed to be treated under the CAT plan. This area includes 425 ha area of catchment which shall be treated by biological / engineering measures and 302 ha area under private land treatment within the free draining catchment.
 - xiv. The command area under 14 villages is being cultivated in Rabi and Kharif crop seasons, though the area sown in Kharif and Rabi is 12.35% and 4% respectively. The crop intensity during Rabi crop has been adopted as 100% of the CCA (6100 ha).Based on Modified Pan Man method for the crop water requirement has been assessed as 25.71 MCM. Micro irrigation by sprinkler system shall be adopted in the entire command area.
 - xv. Under the local area development plan PP has proposed training courses, tailoring, embroidery training centres, computer courses, vocational training, development of public utility as hospitals facilities, sport centres, internal village roads/strengthening community toilets, enhanced medical centre, development of cremation centre, social services like widow grant assistance to physically handicapped, assistance to female marriages and assistance of critically ill persons. For the local area development plan 114 lakh is proposed to be submitted to the collector of the concerned district to manage, monitor, supervise and control the various activities.
 - xvi. The project site is located in seismic Zone III.as per seismic zoning map of India (IS 1893:2002).There are no records of earthquakes, landslides etc. In the area.
 - xvii. The water requirement (200kld) for construction shall be mainly met from the river water and the domestic/drinking water from underground sources.
 - xviii. The total raw material requirement for coarse and fine aggregate and boulder comes to 0.935lakh cum,0.67 lakh cum and 7.33 lakh cum earth and 0.50 lakh cum COT material respectively.
 - xix. Green belt around the reservoir would be created to avoid erosion of soil and prevention of land slips from the banks surrounding the pond. The area for green belt development around reservoir rim shall be about 12 ha over which 18000 saplings would be planted. Along the approach roads plantation will be done on both sides where ever feasible as such plantation of about 6000 saplings will be done. Plantation along roads must consider visibility aspects on curves so as to ensure safe driving. Plantation at the Dam site on either bank in about 2 ha has been proposed for control of erosion and siltation of the stream and aesthetic importance. Plantation (500plants) around the office complexes is proposed to be done so that greenery is developed.
 - xx. **Benefit of the project:** Irrigation potential shall be created in command area villages, Better living Standards for famers of command area, Employment opportunities/to locals in project work and fisheries, Access to improved infrastructure facilities,Recreation and tourism potential may boost Improvement in environment through implementation of CAT, Command Area Development. Compensatory Afforestation, Green belt Development and different other plans. Better oppportunities for cattle rearing. Increase in groundwater level.

- xxi. Total cost of the project is Rs 228.11 Crores in which a provision for land acquisition and Rehabilitation is made for Rs. 67.78 Crores in the estimate.

Based on the information submitted at Para i to xxi above and others, the State Level Environment Impact Assessment Authority (SEIAA) considered the case in its 525th meeting held on 01.03.2019 and decided to accept the recommendations of 340th SEAC meeting held on dtd. 30.01.19.

Hence, Prior Environmental Clearance is accorded under the provisions of EIA notification dtd. 14th September 2006 & its amendments for the proposed " **Bham Medium Irrigation Project at Bham (Rajgarh), Dist. Khandwa, MP Gross Command Area (GCA): 9000 ha; Culturable Command Area (CCA): 6100 ha Catchment area – 193.45 ha** by Executive Engineer, Water Resource Division, Near Harsud Naka, Civil Line, Khandwa, Dist. Khandwa, MP - 450001 MP through Water Resources Department, Superntending Engineer, Office of Engineer-in-Chief, Water Resources Department, Jal Sansadhan Bhawan, Tulsi Nagar, Bhopal 462003, subject to the compliance of the Standard Conditions and the following additional Specific Conditions as recommended by SEIAA & SEAC in its meetings.

A. Specific Conditions as recommended by SEIAA

1. The inputs given by the participants during Public hearing should be properly redressed. All the promises and assurances made during the public hearing shall be fulfilled completely by the water resources department GoMP. The implementation of R & R Plan to be closely monitored to ensure that all project affected families (PAFs) get adequate & timely compensation.
2. Besides the agricultural land, the rehabilitation of public buildings, infrastructures, monument etc. falling in the submergence area should also be included in the rehabilitation plan.
3. A monitoring Committee for R & R shall be constituted which must include representatives of project affected persons including form SC/ST community and at least a woman beneficiary.
4. A grievances redress mechanism is to be devised by WRD GoMP and put in place so that aggrieved PAFs and other stakeholders may approach the Authority easily for resolution of any dispute/conflict.
5. The implementation of Local Area Development Plan (LADP) to be closely monitored.
6. This being a seasonal stream/ river, a minimum environmental flow of 30 % in monsoon season should be released for downstream users.
7. Proposed Compensatory Afforestation programme in propped area shall be taken-up in consultation with State Forest Department. The allocated grant for this purpose shall be fully utilized and not to be diverted for any other purpose. For compensatory afforestation programme, preference shall be given to native species.
8. Proposed Bio-diversity Conservation & Management Plan in EMP report should be implemented with State Forest Department. The allocated budget for this purpose shall be fully utilized and not to be diverted for any other purpose.
9. The catchment Area Treatment (CAT) Plan as proposed in EMP report shall be strictly implemented in consultation with Madhya Pradesh State Forest Department. Major works shall be completed before impounding of reservoir. The financial allocation for CAT Plan implementation shall be fully utilized and not to be diverted for any other purpose.

Catchment Area Treatment Plan as has been proposed should be completed in five years.

10. To enhance the natural environmental quality & aesthetics of project site, greenbelt, as proposed in the EMP Report shall be undertaken in proposed area. Allocated grant for this purpose shall be fully utilised and not to be diverted for any other purpose.
11. Fishery conservation & management plan as proposed shall be implemented in consultation with the Fisheries Department, Government of Madhya Pradesh.. The stocking density of the reservoir shall be around 300 fingerlings per ha. Allocated grant for this purpose shall be fully utilised and not to be diverted for any other purpose.
12. Occurrence of stagnant pools/slow moving water channels during construction and operation of the project may provide breeding source for vector mosquitoes and other parasites. The river should be properly channelized so that no small pools and puddles are allowed to be formed. Even after taking precaution, due to unforeseen situations, breeding of mosquito and resultant malaria or mosquito borne diseases can increase. If such a situation arises, it will be the responsibility of project authorities to take all steps i.e. residual insecticidal spray in all the project area and surrounding 3 km. Area keeping the flight range of mosquitoes in consideration. Also medical assistance to be provided to the affected people at the cost of the developer and appropriate health benefits may be initiated with the help of State Health Department.
13. If the water of reservoir is used for drinking water supply, it should be done after conventional treatment.
14. Regular monitoring of water quality (Surface and Ground) including heavy metals shall be undertaken in the project area and around the project area to ascertain the change, if any, in the water quality due to leaching of contaminants, if any, from the increased use of chemical fertilizers and pesticides.

B. Specific Conditions as recommended by SEAC

(A) PRE-CONSTRUCTION PHASE

1. During any construction/plant erection activity, curtaining of site should be carried out to protect nearby areas.
2. Adequate arrangement to prevent incidence of any endemic health problem due to water /soil borne diseases shall be provided.
3. Adequate provisions for re-vegetation, dressing, resurfacing of burrow pits etc. should be ascertained for protecting soil erosion due to runoff during rain.
4. Burning of firewood/fuel by the construction workers for their cooking may have minor impact on the local air quality, which however can be avoided with provision of alternate cooking fuel such as kerosene or LPG gas.
5. For dust mitigation measures following measures shall be adopted:
 - Roads leading to or at construction sites must be paved and blacktopped (i.e. metallic roads).
 - No excavation of soil shall be carried out without adequate dust mitigation measures in place.

- No loose soil or sand or Construction & Demolition Waste or any other construction material that causes dust shall be left uncovered.
 - Wind-breaker of appropriate height minimum 03 meters shall be provided.
 - Water sprinkling system shall be put in place.
 - Dust mitigation measures shall be displayed prominently at the construction site for easy public viewing.
 - Construction material and waste should be stored only within earmarked area and road side storage of construction material and waste shall be prohibited.
 - No uncovered vehicles carrying construction material and waste shall be permitted.
 - Construction and Demolition Waste processing and disposal site shall be identified and required dust mitigation measures be notified at the site.
6. PP will obtain other necessary clearances/NOC from respective authorities..
 7. Provisions shall be made for the housing of construction/plant erection labor within the site with all necessary infrastructure and facilities such as mobile toilets, mobile STP, safe drinking water, medical health care, crèche etc. The housing may be in the form of temporary structure to be removed after completion of the period.

(B) CONSTRUCTION PHASE

8. PPE's such as helmet, welding shield, ear muffs etc should be provide to the workers during construction/plant erection activities.
9. Fire extinguishers should be provided on site during construction/ plant erection period.
10. Water sprinkling arrangements shall be made to suppress the fugitive emissions and shall ensure that the ambient air quality is well within the prescribed norms by MoEF&CC/CPCB/MPPCB.
11. All the electrical appliances and digging should be minimum 15 meters away from any permanent structure.
12. Properly tuned construction machinery and good condition vehicles with mufflers (low noise generating and having PUC certificate) should be used and turned off which not in use.
13. DG sets (2x 125 KVA) shall be provided with acoustic enclosures to maintain the noise level within the prescribed limits.
14. Waste construction material should be recycles as far as possible and remaining should be disposed off at a designated place in consultation with the local authority.
15. Plantation in patches in suitable land all around the project boundary shall be carried out using tall saplings of minimum 2 meters height of species which are fast growing with thick canopy cover preferably of perennial green nature. As proposed in the landscape plan & EMP. PP will also make necessary arrangements for the causality replacement and maintenance of the plants.
16. MSW of various labors generated during construction/plant erection activities should be disposed off at a designated place in consultation with the local authority.
17. Waste oil & grease generated from the pumps and standby DG sets (2x 125 KVA) should be disposed off in accordance with the Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016 after obtaining authorization.
18. The soil removed during the excavation will be stacked separately and will be used for the green belt development only.

(C) POST CONSTRUCTION/OPERATIONAL PHASE

19. Plantation shall be carried out by the PP as per submitted plan in the command area or on available degraded land.
20. In the post-irrigation phase, farmers tend to use more fertilizers and pesticides these may result in soil and water pollution. Hence, it should be essential to use the fertilizers and pesticides in a judicious manner without causing soil and water pollution. Awareness program shall be conducted and experts should interact with the local people who will guide them on the quantity and proper application of fertilizer and Pesticides.
21. Efficient irrigation systems should be promoted in the command area as Social Responsibility by the trained staff of the department.
22. Periodic soil/water testing shall be carried out in the command area and report to be submitted to Ministry of Agriculture with essential remarks.
23. Use of Solar Energy with LED light arrangement in the pump house, site, office building should be promoted in the project area where ever possible.
24. An energy audit for energy conservation can be performed in pump site, office building, to reduce energy expense and carbon footprints.
25. All leakages will be cleaned out in the pump house to prevent wastage of water with the prescribe procedures in the regular intervals.
26. The public toilets should be made in optimum numbers so that entire command area and site should be open defecation free (ODF).
27. The project authorities should comply with the provisions made in the Water (Prevention & control) of Pollution Act 1974, and amended, Construction and Demolition Waste Management Rules, 2016, Solid Waste Management Rules, 2016, etc.
28. Necessary consents shall be obtained from MPPCB and the air/water pollution control measures have to be installed as per the recommendation of MPPCB.
29. Log-books shall be maintained for disposal of all types hazardous wastes and shall be submitted with the compliance report.
30. The project authorities should comply following provisions/ conditions made in the Construction and Demolition Waste Management Rules, 2016.

(D) ENTIRE LIFE OF THE PROJECT

31. A budgetary provision of Rs. 8701.70 is made for Environmental Management Plan as capital cost and 166.10 Lakh as recurring cost, out of which Rs 41.00 lakh has made for Green Belt Development Plan in the EMP.
32. Wildlife and Bio- diversity Management Plan shall be implemented after the approval of competent authority; Budget of Rs. 25.00 Lakh is made for Wildlife management plan in the EMP
33. No muck disposal shall be done outside of the project site. Rs. 29.00 Lakh is made for Muck Management Plan in EMP. Rs 500.00 Lakh is made for Catchment Area Treatment Plan in EMP. Rs 128.00 Lakh is made for Fisheries Management Plan in EMP.

34. The environment policy of the company should be framed as per MoEF&CC guidelines and same should be complied and monitored through monitoring cell. In case the allocated EMP budget for mitigative measures to control the pollution is not utilized fully, the reason of under utilization of budgetary provisions for EMP should be addressed in annual return.
35. A separate bank account should be maintained for all the expenses made in the EMP activities by PP for financial accountability and these details should be provided in Annual Environmental Statement.
36. All commitments pertaining to public hearing shall be mandatory on part of PP.
37. The environment policy of the company should be framed as per MoEF&CC guidelines and same should be complied and monitored through monitoring cell. In case the allocated EMP budget for mitigative measures to control the pollution is not utilized fully, the reason of under utilization of budgetary provisions for EMP should be addressed in annual return.
38. As proposed, the green belt development / plantation activities should be completed within the first three years of the project and the proposed species should also be planted in consultation with the forest department.
39. In case of any, change in scope of work, technology, modernization and enhancement of capacity/ built-up area/ project area shall again require prior environmental clearance as per EIA notification, 2006.
40. PP shall be responsible for discrepancy (if any) in the submissions made by the PP to SEAC & SEIAA.
41. Land use details of this project.

Sl.No.	Land use	Present		Post-construction	
		Area	%	Area	%
1	Agriculture land	247.62	76.63	242	74.89
2	Dense Forest	40.8	12.63	39.32	12.17
3	Open Forest	2.56	0.79	2.56	0.79
4	Open Scurb/Barren Land	17.9	5.54	16.97	5.25
5	Waterbody	3.57	1.10	12.14	3.75
6	Settlement	10.67	3.30	10.67	3.30
Total		323.12	100.00	323.12	100.00

42. The validity of the EC shall be as per the provisions of EIA Notification subject to the following: Expansion or modernization in the project, entailing capacity/ built-up area/ project area, addition with change in process and or technology and any change in product - mix in proposed mining unit shall require a fresh Environment Clearance.

Standard Conditions:

1. Adequate arrangements for providing free fuel like kerosene/wood/LPG shall be made at the project cost for the labors engaged in the construction work so that indiscriminate felling of trees is prevented.
2. The laborers to be engaged for construction works shall be thoroughly examined by health personnel and adequately treated before issuing them work permit.
3. Water sprinkling arrangements shall be made to suppress the fugitive emissions and shall ensure that the ambient air quality is well within the prescribed norms by MoEF/CPCB.

4. Potable drinking water and proper sanitary facilities shall be provided for the labor force.
5. Consolidation and compilation of the muck should be carried-out in the muck dump sites and the dump sites should be above high flood level. Restoration of construction area including dumping sites of excavated materials shall be ensured by leveling, filling up of borrow pits, landscaping etc. The area should be properly treated with suitable plantation.
6. The Regional Office of MoEF, GoI, Bhopal & MPPCB shall monitor compliance of the stipulated conditions. A complete set of documents including Environment Impact Assessment Report, Environmental Management Plan and Monitoring Plan should be given to Regional Office, MoEF, GoI, Bhopal & MPPCB. The project proponent shall provide full cooperation during their inspection and all required documents/data to the officials.
7. Action plan with respect to suggestion/improvement and recommendations made and agreed during public hearing consultation shall be submitted to the Regional Office, MoEF, GoI, Bhopal, MPPCB within six months.
8. The responsibility of implementation of environmental safeguards and RR plan rests fully with the Water Resources Department GoMP and Government of Madhya Pradesh. The WRD Government of Madhya Pradesh should also monitor implementation of EMP at regular intervals preferably at the level of Principal Secretary.
9. Necessary livelihood plan for oustees is to be prepared, if found necessary, in consultation with State Government Departments concerned. The Water Resources Department Government of Madhya Pradesh should submit compliance on this components & also while submitting six monthly compliance report to MoEF, GoI, Regional Office, Bhopal.
10. PP should ensure implementation of all activities / mitigative measures / safeguards proposed in the Environmental Impact Assessment (EIA) report and Environmental Management Plan (EMP) approved by SEAC and other reports from time to time must.
11. All parameters listed in Environmental Monitoring Plan approved by SEAC must be monitored at approved locations and frequencies.
12. The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically.
13. The monitored data for criteria pollutant levels, namely; SPM, RSPM, SO₂, NO_x (ambient levels) or critical sectoral parameters, indicated for the project shall be monitored and displayed at a convenient location near the dam site in the public domain.
14. The sewage or waste water should be properly collected, treated so as to conform to the standards prescribed by MoEF & CPCB. The treated effluents conforming to the prescribed standards shall be re-circulated and reused for horticulture / plantation.
15. Conjunctive use of surface water has to be planned and implemented in the project to check water logging as well as to increase productivity.
16. The equipment likely to generated high noise levels during construction period or otherwise shall have to meet the ambient noise level standards as notified under the Noise Pollution (Regulation and Control) Rules, 2000 as amended from time to time

- under the Environment Protection Act (EPA), 1986. Workers shall be provided with ear plugs / muffs.
17. The Project Proponent has to submit half yearly compliance report of the stipulated terms and conditions in the Prior Environmental Clearance, including the results of monitored data in hard and soft copy to the Regulatory Authority, respective Zonal Office of CPCB and the SPCB and Regional Office of MoEF, Gol at Bhopal on 1st June and 1st December of each calendar year.
 18. A separate Environmental Management Cell with suitable qualified personnel shall be set-up under the control of a Senior Executive, who will report directly to the Head of the Organization.
 19. Adequate financial provision should be made in the total budget of the project for implementation of the above suggestion safeguard measures. The funds earmarked for environmental protection measures shall be kept in separate account and shall be fully utilized for the said purpose and not to be diverted for other purpose. Year wise expenditure shall be reported to the MoEF, Gol, Regional Office located at Bhopal, CPCB & MPCB. In case of revision of the project cost due to price level change the cost of EMP shall also be updated proportionately and revised upwardly.
 20. On-farm development (OFD) works are to be completed by the project proponent simultaneously and before the commencement of irrigation. WUA's (Water Users Associations) should be made functional to undertake the OFD works. Special & critical monitoring of progress to be undertaken by the Water Resources Department GoMP to ensure that OFD works are completed along with main canal networks.
 21. Details of land holding of project affected persons whose land is being acquired shall be submitted to MoEF&CC, Gol, Regional Office. The R & R benefits for the land losing households will be as per the National Rehabilitation and Resettlement Policy, 2007 or as per the State Rehabilitation and Resettlement Policy, whichever is more beneficial to the project affected villages. The R & R issues shall be completed before commissioning of the project. In case latest Act of 2014 is applicable, the same Act is to be followed.
 22. The MP SEIAA or any other competent authority reserves the right to alter/modify or add additional, safeguard measures subsequently, if found necessary and to take action, including revoking of the clearance under provisions of the environment (Protection) Act 1986 to ensure effective implementation of the suggested safeguard measures in a time bound and satisfactory manner.
 23. The Prior Environmental Clearance letter is valid for a period of 10 years from the date of issue of this letter for commissioning of the project.
 24. A copy of the Prior Environmental Clearance issued by MP SEIAA shall be submitted by the Project Proponent to the Heads of the Local Bodies, Panchayat / Zila Parishad / Municipal Bodies as applicable, local NGO, if any, in addition to the associated Government Department from whom any suggestion / representations were received while processing the proposal and those responsible for controlling the proposed project, who in turn has to display the same for 30 days from the date of receipt. The clearance letter shall also be put on website by the project proponent.
 25. State Pollution Control board / committee shall display a copy of the clearance letter at the regional office, district industries centre and collector's/tehsildar's office for 30 days.


26. The Project Proponent shall advertise at least in two local newspapers widely circulated in the region around the project, one of which shall be in the vernacular language of the locality concerned, within 7 days of the issue of the clearance letter informing that the project has been accorded environmental clearance and a copy of the clearance letter is available with the State Pollution Control Board and also at web site of the State Level Environment Impact Assessment Authority (SEIAA) website at www.mpseiaa.nic.in and copy the same shall be forwarded to the Regional Office, MoEF&CC, GoI, Bhopal.
27. After 5 years of the commissioning of the project a study shall be undertaken regarding impact of the project on the environment and downstream ecology. The study shall be undertaken by an independent agency to be decided in consultation with the Ministry / authority.
28. A multi disciplinary committee (MDC) for monitoring the implementation of environmental safe guards during construction shall be constituted by the project proponent (PP) in consultation with the state environment ministry as early as possible. A panel may be proposed by the PP and submitted to ministry. The Project Proponent shall organize six monthly meetings of the committee and submit the monitoring report to the ministry.
29. Occupational health and safety measures for the workers including identification of work related health hazards, training on malaria eradication, HIV, and health effects on exposure to water borne diseases shall be carried out. Periodic monitoring for the workers shall be conducted and records maintained including health records of the workers. Awareness programme for workers on impact on their health and precautionary measures like use of personal equipments etc. shall be carried out periodically. Review of impact of various health measures shall be conducted followed by follow up action wherever required.
30. The Project Proponent shall provide proper arrangement for the disposal of hazardous waste (if any) and obtain authorization under Hazardous Waste (Management Handling & Transboundary Movement) Rules from MPPCB.
31. The above conditions will be enforced inter-alia, under the provisions of the Water (Prevention & Control of Pollution) Act, 1974, the Air (Prevention & Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and the Public Liability Insurance Act, 1991 along with amendments and rules.
32. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the Regional Office of MoEF.
33. Any other clearance required from any other organization / department should be obtained before commencement of works and commissioning of the project, as applicable.
34. Concealing factual data or submission of false / fabricated data and failure to comply with any of the conditions mentioned above may result in withdrawal of this clearance and attract action under the provisions of Environment (Protection) Act, 1986.

35. Any appeal against this prior environmental clearance shall lie with the Green Tribunal, if necessary, within a period of 30 days from the date of issue, as prescribed under Section 10 of the National Green Tribunal Act 2010.

2832


Endt No. / SEIAA/ 2019

Dated 28.3.19


(Jitendra Singh Raj)
Member Secretary

Copy to:-

- (1). Principal Secretary, Urban Development & Environment Deptt. 3rd Floor, Mantralaya Vallabh Bhawan, Bhopal.
- (2). Secretary, SEAC, Research and Development Wing Madhya Pradesh Pollution Control Board, Paryavaran Parisar, E-5, Arera Colony Bhopal-462016.
- (3). Member Secretary, Madhya Pradesh Pollution Control Board, Paryavaran Parisar, E-5, Arera Colony, Bhopal-462016.
- (4). The Collector, Distt- Khandwa (M.P.).
- (5). Engineer-in-Chief, Water Resources Department, Jal Sansadhan Bhawan, Tulsi Nagar, Bhopal (MP)
- (6). The Principal Chief Conservator of forest, Ground floor Satpuda Bhawan, Bhopal (M.P)
- (7). Director, I.A. Division, Monitoring Cell, MoEF, GoI, Ministry of Environment & Forest Indira Paryavaran Bhawan, Jor Bagh Road, New Delhi – 110 003
- (8). Director (S), Regional office of the MOEF, (Western Region), Kendriya Paryavaran Bhawan, Link Road No. 3, Ravi Shankar Nagar, Bhopal-462016.
- (9). Guard file.


(Dr. Sanjeev Sachdev)
Officer-in-Charge