

# State Environment Impact Assessment Authority, M.P. (Government of India, Ministry of Environment & Forests)

Environmental Planning Coordination Organization (EPCO)
Paryavaran Parisar, E-5. Arera Colony
Bhopal-4620 16
visit us http://www.mpseiaa.nic.in

Tel:0755-2466970, 2466859

Fax: 0755-2462136

No: 270 /SEIAA/2016 Date: 25.7. /⟨

To, Shri Suresh Kumar, Chief Executive Officer, Gwalior Development Authority, Vikas Bhawan, 1 Ravi Nagar, Gwalior (MP)- 474002

Sub:- Case No. 4931/2016 Prior Environment Clearance for proposed Construction of affordable Housing Project "Atal Ashray Yojna" at Survey No. 322, 323, 324, 325, 326, Village Jazderua Kalan, Tehsil & District - Gwalior, M.P.; Total Project Area – 24750 sq.m., Built- up Area–42898.23 sq.m. (FAR 37124 sq.m.) by Shri Suresh Kumar CEO, Gwalior Development Authority, Vikas Bhawan, 1 Ravi Nagar Gwalior (MP)-474002, E-mail id – ceo@ gdagwalior.com, Phone No. 0751-2445536, ENV Development Assistance Systems Pvt. Ltd., Lucknow,

Ref: Your application dtd. 04.01.2016 received in SEIAA office on 12.01.2016

With reference to above, the proposal has been appraised as per prescribed procedure & provisions under the EIA notification issued by the Ministry of Environment & Forests vide S.O. 1533 (E), dated 14<sup>th</sup> September 2006 and its amendment, on the basis of the mandatory documents enclosed with the application viz., Form I, Form IA, Conceptual Plan, drawings, ppt & the additional clarifications furnished in response to the observations by the State Expert Appraisal Committee (SEAC) and State Environment Impact Assessment Authority (SEIAA) constituted by the competent Authority.

- (i). The proposed project is building & construction residential housing project "Atal Ashray Yojna" having total built up area 42898.23 sq.m. The project comes under 8(a) category (B) of schedule of EIA Notification, 2006 because total construction is between 20,000 sq.m & 1,50,000 sq.m and plot area is less than 50 ha.
- (ii). As per the T & CP Gwalior (vide letter no. 2388 dtd 11.11.14) the total land area is 24750.0 sq.m. at Village Jazderua Kalan, Tehsil & District - Gwalior. As per Khasra Panchsala 2014-2015 and collector order dtd. 21.10.2014the land is the name of Gwalior Development Authority for Atal Ashray Yojna Gwalior Madhya Pradesh. The project includes Residential unit- 576 (EWS Unit 192 & LIG Unit 384), Convenient Shops, Health centre and School building etc.
- (iii). The source of water supply is Municipal Corporation, Gwalior (letter no. 147 dtd. 15.02.2016). The total water requirement is 430 KLD (fresh water 268 KLD). The waste water generation is 365 KLD and STP capacity is 440 KLD. The available treated water is 320 KLD out of which 162 KLD will be recycled and remaining 180 KLD proposed to be disposed off in the PHED sewer line. PP has submitted letter (dtd. 09.11.2015) from Commissioner, Municipal Corporation, Gwalior for disposal of extra treated waste water.

Case No. 4931/2016
Issued vide letter no 2710 -11... dated ... 25... 16
Case No.: To be quoted in registered cases for correspondence

7 1 of 5


- (iv). The Municipal Solid Waste 1543 kg/day, shall be generated. The generated biodegradable and non biodegradable waste will be collected separately and temporarily stored at MSW site along with STP Sludge. The bio degradable waste proposed to dispose to MSW site for composting and non-biodegradable waste, will be deposited at a landfill site of Municipal Corporation. PP has submitted letter (dtd. 09.11.2015) from Municipal Corporation, Gwalior for disposal of solid waste.
- (v). The maximum height of the building is 12.0 m. PP has provided one traffic entry from 18m wide road on east of the project and 12m wide road located in south of project. Internal roads are having width of 12m and 7.5m respectively.
- (vi). PP has proposed to provide fire water storage tank, portable fire extinguisher of 10 ltr carrying capacity, hose reel, yard hydrant system, wet riser system, automatic sprinkler system, & manual fire alarm system etc. as per NBC 2005.
- (vii). PP has proposed Parking space of 5773.23 sq.m. (290 ECS for two wheeler and 96 ECS for four wheelers)
- (viii). The total power requirement is 1500 KVA. The source of electricity is Madhya Pradesh Kshetra Vidyut Vitran Company Limited. PP has also proposed DG set of capacity 1x50 KVA. For energy conservation measures PP has proposed use of LED in common area & landscape area.
  - (ix). PP has proposed to provide roof top rain water harvesting system with 05 nos. of recharging pits.
  - (x). PP has proposed an area of 2780 sq.m (11.23%) to be developed as green area by planting nos of trees 200.

Based on the information submitted at Para i to x above and others, the State Level Environment Impact Assessment Authority (SEIAA) considered the case in its 348<sup>th</sup> meeting held on 02.07.2016 and decided to accept the recommendations of SEAC meetings 277<sup>th</sup> dtd 31.05.2016.

Hence, Prior Environmental Clearance is accorded under the provisions of EIA notification dtd. 14<sup>th</sup> September 2006 and its amendments to the proposed Construction of affordable Housing Project "Atal Ashray Yojna" at Survey No. 322, 323, 324, 325, 326, Village Jazderua Kalan, Tehsil & District - Gwalior, M.P.; Total Project Area – 24750 sq.m., Built- up Area–42898.23 sq.m. (FAR 37124 sq.m.) by Shri Suresh Kumar CEO, Gwalior Development Authority, Vikas Bhawan, 1 Ravi Nagar Gwalior subject to the compliance of the Standard Conditions enclosed at Annex-I and the following additional Specific Conditions as recommended by SEIAA & SEAC in its meetings.

### A. Specific Conditions as recommended by SEIAA:-

- (1) The entire demand of water should be met through Municipal Corporation and there should be no extraction of ground water. PP should ensure to lay down the pipeline connection from project site to municipal sewer line to meet up the fresh water requirement.
- (2) The inlet and outlet point of natural drain system should be maintained with adequate size of channel for ensuring unrestricted flow of water.
- (3) Waste water management:-
  - (a) PP should ensure linkage with municipal sewer line for disposal of waste water.
  - (b) The treated wastewater of 162 KLD shall be recycled and reused for flushing (138 KLD) and other (24 KLD) to reduce the demand of fresh water as committed.



- (c) Project Proponent shall ensure regular operation and maintenance of the STP.
- (d) The Project Proponent shall explore the possibilities of reusing the treated wastewater from nearby projects or disposed off to STP (50 MLD capacities) of PHE Department adjacent to the project area.
- (4) Solid Waste Management:-
  - (a) Ensure linkage with Municipal Corporation for final disposal of MSW.
  - (b) Provide compactors for MSW.
  - (c) Separate wet and dry bins must be provided for facilitating segregation of waste.
  - (d) All non-biodegradable waste shall be handed over to authorized recyclers for which a written tie up must be done with the authorized recyclers.
  - (e) The construction materials and debris shall be properly stored and handled to avoid negative impacts such as air pollution and public nuisances by blocking the roads and public passages.
  - (f) A 48 hours solid waste storage facility in covered area should be provided.
- (5) PP should ensure road width, front MOS and side / rear as per MPBVR 2012.
- (6) For firefighting:-
  - (a) PP should ensure connectivity to the fire station from the project site.
  - (b) Underground fire water storage tanks of adequate capacity shall be provided as proposed.
  - (c) Dedicated power back up system shall be provided in the case of power failure & emergency of fire water pumps.
- (7) For Rain Water Harvesting, and Ground water recharge:-
  - (a) Rain water harvesting from rooftop and paved areas and ground water recharge through 5 nos. of recharging pit shall be carried out as per the details submitted. In addition, PP should provide recharging trenches. The base of the trenches should be Kachha with pebbles.
  - (b) Before recharging the runoff, pre-treatment must be done to remove suspended matter.
  - (c) The unpaved area shall be more than or equal to 20% of the recreational open spaces.
- (8) Energy:-
  - (a) All common area lighting must be of LED/Solar lights.
  - (b) At least 1% of connected applied load generated from renewable energy source such as photovoltaic cells or wind mills or hybrid be provided.
  - (c) The project proponent shall install energy efficient devices, appliances, motors and pumps conforming to the Bureau of Energy Efficiency norms.
  - (d) Solar lights shall be provided in the open sunlit areas.
  - (e) Maximization of use of natural lighting through building design.
  - (f) Passive solar cooling, utilizing building shading through overhangs.

3 of 5

Case No. 4931/2016
Issued vide letter no 2.71 and dated 5.71/6
Case No.: To be quoted in registered cases for correspondence

(g) DG set will be provided with auto cut controlled mechanism for STP and Other common services

#### (9) Parking:

- (a) Parking space of 5773.23 sq.m. (290 ECS for two wheeler and 96 ECS for four wheelers) shall be provided as proposed.
- (b) The area earmarked for the parking shall be used for parking only. No other activity shall be permitted in this area.

#### (10) Air Quality and Noise :-

- (a) Dust, smoke & debris prevention measures such as wheel washing, screens, barricading & debris chute shall be installed at the site during construction including plastic/tarpaulin sheet covers for trucks bringing in sand & material at the site.
- (b) The exhaust pipe of the DG set if installed must be minimum of 10mtr away from the building or in case it is less than 10m away, the exhaust pipe shall be taken up to 6m above the building.
- (c) Use of diesel generator sets during construction phase shall be strictly with acoustic enclosure and shall confirm to EPA Rules for air and noise emission standards.
- (d) The gaseous emissions from the D.G. Sets shall conform to the standards prescribed by MPPCB. At no time, the emission levels shall go beyond the stipulated standards.

#### (11) Green belt :-

- (a) Green belt area of 2780 sq.m (11.23%) comprising of 200 numbers of trees shall be developed as proposed.
- (b) PP should ensure two rows peripheral plantation at a distance of 3 to 5 m. of tree species (2 mt. high plants) all around the property area. Avenue plantation along the roads and formal garden area, trees of indigenous local varieties like Neem, Peepal, Kadam, Karanj, Kachnaar etc. should be planted.
- (c) PP should ensure to initiate plantation in the project site during construction.
- (d) Every effort should be made to protect the existing trees on the plot.
- (e) The green belt design along the periphery of the plot shall achieve attenuation factor confirming to the day and night noise standards prescribed for residential land use. The open spaces inside the plot should be suitably landscaped and covered with vegetation of indigenous variety.
- (12) The project authorities shall earmark adequate funds to implement the conditions stipulated by SEIAA/SEAC along with the implementation schedule for all the conditions stipulated herein. The funds so provided shall not be diverted for any other purpose.

#### B. Specific Conditions as recommended by SEAC:-

- (13) The excess treated water will be used for watering of municipal road side green area or efforts shall be made to supply this water to the construction sites for use in the construction works.
- (14) Peripheral plantation all around the project boundary shall be carried out using tall saplings of minimum 2 meters height of species which are fast

4 of 5

 growing with thick canopy cover preferably of perennial green nature. As proposed in the landscape plan & EMP a minimum of 200 no of trees will be planned in residential area. PP will also make necessary arrangements for the causality replacement and maintenance of the plants.

- (15) STP sludge shall be filter-pressed and the de-watered sludge shall be disposed off with the MSW.
- (16) Power back-up for un-interrupted operations of STP shall be ensured.
- (17) CFL/LED should be preferred over of tube lights.
- (18) Fund should be exclusively earmarked for the implementation of EMP.
- (19) MSW storage area should have 48 hours storage capacity.
- (20) Dual plumbing should be provided.
- (21) Provision for physically challenged persons be made so that they easily excess pathway/derive way for their vehicles.
- (22) Provisions shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile STP, safe drinking water, medical health care, crèche etc. The housing may be in the form of temporary structure to be removed after completion of the period.
- (23) PP will obtain other necessary clearances/NOC from concerned authorities.
- (24) Revised plantation scheme and Revised parking plan, submitted by PP vides their letter dated 25/04/2016 should be implemented.

Standard Conditions - Encl: Annex-I

(Anupam Rajah)
Member Secretary

2711

Endt No. / SEIAA/2016

Date 25.7. 6

Copy to:-

- Principal Secretary, Urban Development & Environment Deptt. 3<sup>rd</sup> Floor, Mantralaya Vallabh Bhawan, Bhopal.
- Secretary, SEAC, Research and Development Wing Madhya Pradesh Pollution Control Board, Paryavaran Parisar, E-5, Arera Colony Bhopal-462016.
- (3). Member Secretary, Madhya Pradesh Pollution Control Board, Paryavaran Parisar, E-5, Arera Colony, Bhopal-462016.
- (4). The Collector, District Gwalior, M.P.
- (5). The Commissioner, Municipal Corporation, Gwalior, MP
- (6). The Town & Country Planning District Office, Gwalior, MP
- Director, I.A. Division, Monitoring Cell, MoEF, Gol, Ministry of Environment & Forest Indira Paryavaran Bhawan, Jor Bagh Road, New Delhi – 110 003
- (8). Director (S), Regional office of the MOEF, (Western Region), Kendriya Paryavaran Bhawan, Link Road No. 3, Ravi Shankar Nagar, Bhopal-462016.

(9). Guard file.

Encl: Standard Conditions (Annex-I)

(Dr. Sanjeev Sachdev)
Officer-in-Charge

(Government of India, Ministry of Environment & Forests)
Research and Development Wing, Madhya Pradesh Pollution Control Board,
Paryavaran Parisar, E-5. Arera Colony, Bhopal-4620 16

Annex-I

Standard Conditions related to under item 8 (a) & 8 (b) of the schedule of EIA notification, 2006 (Building/ construction projects / area development projects & township)

#### A. Construction Phase

- The construction site shall be provided with adequately barricades of at least 3 m height on its periphery with adequate signage.
- 2. All required sanitary and hygienic measures should be in place before starting any construction work and are to be maintained throughout the project phase.
  - 3. Provision shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, safe drinking water, medical health care, crèche etc. The housing may be in the form of temporary structures to be removed after the completion of the project.
  - 4. Occupational health and safety measures for the workers including identification of work related health hazards, training on malaria eradication, HIV, and health effects on exposure to dust etc. shall be carried out. Periodic monitoring for exposure to respirable dust on the workers shall be conducted and records maintained including health records of the workers. Awareness programme for workers on impact of dust on their health and periodically.
  - A First Aid Room will be provided in the project both during construction and operation of the project.
- 6. All the topsoil excavated during construction activities should be stored for use in horticulture/landscape development within the project site.
- Disposal of muck during construction phase should not create any adverse effect on the neighbouring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.
- Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
- Construction spoils, including bituminous material and other hazardous materials, must not be allowed to contaminate water courses and the dump sites for such material must be secured so that they should not leach into the ground water.

 Any hazardous waste generated during construction phase, should be disposed off as per applicable rules and norms with necessary approvals of the M.P. Pollution Control Board

(Dr R P Singh) Officer-in-Charge

(Dr Vinita Vipat) Officer-in-Charge

(Dr Sadhna Tiwari) Officer-in-Charge 1 of 6

Issued Vide 2710-14-1AXEFED

0

(Government of India, Ministry of Environment & Forests) Research and Development Wing, Madhya Pradesh Pollution Control Board, Paryavaran Parisar, E-5. Arera Colony, Bhopal-4620 16

- 11. The dlesel generator sets (if any) to be used during construction phase should be low sulphur diesel type and should conform to Environment (Protection) Rules prescribed for air and noise emission standards.
- 12. The diesel required (if any) for operating DG sets shall be stored in underground tanks and if required, clearance from Chief Controller of Explosives shall be taken.
- 13. Wastewater generated from temporary leabour tents will be diverted to the sewer network
- 14. No water logging should take place at any point during construction phase.
- 15. If the project site is located within the 100 km of Thermal Power Stations, then fly ash should be used as building material in the construction as per the provisions of Fly ash Notification of September, 1999 and amended as on 27th August, 2003.
- 16. As far as possible ready mixed concrete should be used in construction work.
- 17. Vehicles hired for bringing construction material to the site should be in good condition and should have a pollution check certificate and should conform to applicable air and noise emission standards and should be operated only during non-peak hours.
- 18. Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/ MPPCB.
- 19. Storm water control and its use should be as per CGWB and BIS standards for various
- 20. Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices referred.
- 21. Care shall be taken during the wet drilling activities.
- 22. Spread of contaminated water should be prevented by installing temporary barriers of
- 23. To prevent surface and ground water contamination by oil/grease, leak proof containers shall be used for storage and transportation of oil/grease. The floors of oil/grease handling area will be kept effectively impervious.
- On-site burning of waste material will not be permitted.
- 25. Ground water should not be used during construction phase. Private tanker water suppliers may be asked to supply water during construction phase.
- Commitment towards CSR have to be followed strictly.

27. Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.

(Dr R P Singh 3.4" Officer-in-Charge

(Dr Vinita Vipat) Officer-in-Charge

(Dr Sadhna Tiwari)

2 of 6

Officer-in-Charge

Issted William & 7 (0+MVIPGPCO

(Government of India, Ministry of Environment & Forests)
Research and Development Wing, Madhya Pradesh Pollution Control Board,
Paryavaran Parisar, E-5. Arera Colony, Bhopal-4620 16


- 28. Wherever possible, the area around the STP / ETP should be surrounded with dense green belt.
- 29. To reduce the electricity consumption and load on air conditioning, high quality double glass with special reflective coating in windows should be promoted.
- 30. Roof should meet prescriptive requirement as per Energy Conservation Building Code by using appropriate thermal insulation material to fulfill requirement.
- 31. Opaque wall should meet prescriptive requirement as per Energy Conservation Building Code which is proposed to be mandatory for all air-conditioned spaces while it is aspirational for non-air conditioned spaces by use of appropriate thermal insulation material to fulfill requirement.
- 32. Approval of the competent authority shall be obtained for structural safety of the buildings due to earthquake, adequacy of fire fighting equipments, etc. as per National Building Code including protection measures from lightening etc.

#### B. Operation Phase

- 1. The installation of the Sewage Treatment Plant (STP) as submitted by PP in the office of SEIAA should be certified by an independent expert and a report in this regard should be submitted to the Regional office of the Ministry of Environment & Forest, Gol before the project is commissioned for operation. Treated effluent discharge from STP shall be recycled/reused to the maximum extent possible. Treated effluent shall conform to the norms and standards of the M.P. Pollution Control Board. Necessary measures should be made to mitigate the odour problem from STP.
- Treated waste water should not be used for air conditioning.
- 3. Treatment of 100% grey water by decentralized treatment should be done.
- The bio-medical waste (if applicable) generated should be disposed off as per the provisions of Bio-medical waste (Management and Handling) Rules 1988 as amended till date.
- Provision of separate entrance / exit gate should be made for collection of segregated bio-medical waste (if applicable) from the storage area.
- The solid waste generated should be properly collected and segregated. Wet garbage should be composted and dry/inert solid waste should be disposed off to the approved sites for land filling after recovering recyclable material as per CPCB norms.
- 7. Diesel power generating sets if proposed as source of back up power for elevators and common area illumination during operation phase should be of enclosed type and confirm to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Low sulphur diesel must be used. The location of the DG sets may be decided with in consultation with Madhya Pradesh Pollution Control Board.

(Dr R P Singh) Officer-in-Charge

(Dr Vinita Vipat) Officer-in-Charge (Dr Sadhna Tiwari) Officer-in-Charge 3 of 6



(Government of India, Ministry of Environment & Forests)
Research and Development Wing, Madhya Pradesh Pollution Control Board,
Paryavaran Parisar, E-5. Arera Colony, Bhopal-4620 16

- 8. No water logging should take place at any point during operation phase.
- The Project Proponent shall explore the possibility of using solar energy wherever possible.
- 10. Provision for plantation has to be made as per Madnya Pradesh Bhumi Vikas Niyam,
  - 11. Any hazardous waste generated during operation phase, should be disposed off as per applicable rules and norms with necessary approvals of the M.P. Pollution Control Board.
  - Noise should be controlled to ensure that it does not exceed the prescribed standards of CPCB.
  - 13. Weep holes in the compound walls shall be provided to ensure natural drainage of rain water in the catchment area during the monsoon period.
  - 14. Rain water harvesting for roof run- off and surface run- off, should be implemented. Before recharging the surface run off, pre-treatment must be done to remove suspended matter, oil and grease. The bore well for rainwater recharging should be kept at least 5 mts. above the highest ground water table.
  - The ground water level and its quality should be monitored regularly in consultation with Central Ground Water Authority.
  - 16. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
  - 17. A Report on the energy conservation measures confirming to energy conservation norms finalize by Bureau of Energy Efficiency should be prepared incorporating details about building materials & technology, R & U Factors etc and submit to the Regional office of Ministry of Environment & Forest, Gol in three months time.
  - 18. Energy conservation measures like installation of CFLs/TFLs for the lighting the areas outside the building should be integral part of the project design and should be in place before project commissioning. Used CFLs and TFLs should be properly collected and disposed off/sent for recycling as per the prevailing guidelines/ rules of the regulatory authority to avoid mercury contamination. Use of solar panels may be done to the extent possible.
  - 19. The building should have adequate distance between them to allow movement of fresh air and passage of natural light, air and ventilation.
  - The area earmarked for the parking shall be used for parking only. No other activity shall be permitted in this area.
  - Ozone Depleting Substances (Regulation & Control) Rules shall be followed while designing the air conditioning system (if any) of the project.

(Dr R P Singh) Officer-in-Charge (Dr Vinita Vipat) Officer-in-Charge

(Dr Sadhna Tiwari) Officer-in-Charge 4 of 6

Dated Vide No 2 312-11 AMEPED CO

(Government of India, Ministry of Environment & Forests)
Research and Development Wing, Madhya Pradesh Pollution Control Board,
Paryavaran Parisar, E-5. Arera Colony, Bhopal-4620 16

#### C. Others

- All activities / mitigative measures proposed by PP in Environmental Impact Assessment (if applicable) and approved by SEAC must be ensured.
- All activities / mitigative measures proposed by PP in Environmental Management Plan and approved by SEAC must be ensured.
- All parameters listed in Environmental Monitoring Plan approved by SEAC must be monitored at approved locations and frequencies.
- Project Proponent has to strictly follow the direction/guidelines issued by MoEF, CPCB and other Govt. agencies from time to time.
- The funds earmarked for environmental protection measures shall be kept in separate account and shall not be diverted for other purpose. Year wise expenditure shall be reported to the MoEF, GoI, and its Regional Office located at Bhopal.
- The Ministry or any other competent authority may alter/modify the conditions or stipulate any further condition in the interest of environment protection.
  - The Environmental Clearance shall be valid for a period of five years from the date of issue of this letter.
- The project proponent shall also submit six monthly reports on 1<sup>st</sup> June and 1<sup>st</sup> December
  of each calendar year on the status of compliance of the stipulated EC conditions
  including results of monitored data to the regulatory Authority in hard and soft copies.
- The Regional Office, MoEF, Gol, Bhopal and MPPCB shall monitor compliance of the stipulated conditions. A complete set of documents including Environment Impact Assessment Report. Environmental Management Plan and other documents information should be given to Regional Office of the MoEF, Gol at Bhopal and MPPCB.
- 10. The Project Proponent shall inform to the Regional Office, MoEF, Gol, Bhopal and MP PCB regarding date of financial closures and final approval of the project by the concerned authorities and the date of start of land development work.
- In the case of expansion or any change(s) in the scope of the project, the project shall again require prior Environmental Clearance as per EIA notification, 2006.
- 12. The SEIAA of M.P. reserves the right to add additional safeguard measures subsequently, if found necessary, and to take action including revoking of the environment clearance under the provisions of the Environmental (Protection), Act, 1986, to ensure effective implementation of the suggested safeguard measures in a time bound and satisfactory manner.
- 13. All other statutory clearances such as the approvals for storage of diesel from Chief Controller of Explosives, Fire Department, Civil Aviation Department, Forest Conservation Act, 1980 and Wildlife (Protection) Act, 1972 etc. shall be obtained (as and when applicable), by the project proponent from the respective competent authorities.

(Dr R P Singh)
Officer-in-Charge

(Dr Vinita Vipat) Officer-in-Charge

(Dr Sadhna Tiwari) Officer-in-Charge 5 of 6

Issued Vide No & Alo-1) EJAA/EPCO Daled & 7.16

(Government of India, Ministry of Environment & Forests)
Research and Development Wing, Madhya Pradesh Pollution Control Board,
Paryavaran Parisar, E-5. Arera Colony, Bhopal-4620 18

- 14. These stipulations would be enforced among others under the provisions of Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and control of Pollution) act 1981, the Environment (Protection) Act, 1986, the Public Liability (Insurance) Act, 1991 and EIA Notification, 2006.
- 15. The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM, SO<sub>2</sub>, NOx (ambient levels as well as stack emissions) or critical sectoral parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company and in the public domain.
- 16. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the Regional Office of MoEF.
- 17. Concealing factual data or submission of false/fabricated data and failure to comply with any of the conditions mentioned above may result in withdrawal of this clearance and attract action under the provisions of Environment (Protection) Act, 1986.
- 18. A copy of the environmental clearance shall be submitted by the Project Proponent to the Heads of the Local Bodies, Panchayat and municipal bodies as applicable in addition to the relevant officers of the Government who in turn has to display the same for 30 days from the date of receipt.
- 19. The Project Proponent shall advertise at least in two local newspapers widely circulated, one of which shall be in the vernacular language of the locality concerned, within 7 days of the issue of the clearance letter informing that the project has been accorded environmental clearance and a copy of the clearance letter is available with the State Pollution Control Board and also at website of the State Level Environment Impact Assessment Authority (SEIAA) at www.mpseiaa.nic.in and a copy of the same shall be forwarded to the Regional Office, MoEF, Gol, Bhopal.

20. Any appeal against this prior environmental clearance shall lie with the Green Tribunal, if necessary, within a period of 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.

(Dr R P Singh)

Officer-in-Charge

(Dr Vinita Vipat) Officer-in-Charge

(Dr Sadhna Tiwari) Officer-in-Charge 6 of 6

Dated Vide No. 27.16 SEIANEPCO