

# State Environment Impact Assessment Authority, M.P.

(Ministry of Environment, Forest and Climate Change, Government of India)

## **Environmental Planning & Coordination Organization**

Paryavaran Parisar, E-5, Arera Colony Bhopal - 462016

visit us http://www.mpseiaa.nic.in Email: mpseiaa@gmail.com

Tel.: 0755 - 2466970, 2466859 Fax: 0755 - 2462136

No.: 9630 ISEIAA/ 20 Date: 29/0.26

To,

Mr. Rajendra Kumar Mansukhani, Partner M/s Man Developments, G-9, Man Heritage, 6/2, South Tukoganj, Indore, MP - 452001

Sub:- Case No. 5689/2018: Environment Clearance for "Group Housing Project "Royal Amar Greens" at Khasra No. 37/1/2, 38/1, 38/2 min 1, 38/2 min 2, 38/2 min 3, 38/2 min 4, 38/2 min 5, 39/1/1, 39/1/2, 39/1/3, 39/2 min 1, 39/2 min 2, 39/2 min 3, 39/2 min 4 and 39/2 min 5 Village Niranjanpur Tehsil & District Indore M.P. Total Plot Area: 20350.0 m 2 Net Plot Area: 19405.0 sq.m Built-up Area: 67100.423 sq.m Built-up Area Constructed: 34526.54 sq.m by M/s Man Developments through Partner Mr. Rajendra Kumar Mansukhani G-9, Man Heritage, 6/2 South, Tukoganj, Indore (M.P.) - 452001 E-mail info@mandevelopments.co.in Telephone No. +91-98270-29900 Envt. Consultant: EQMS India Pvt. Ltd.

Ref: Your application dtd.07.05.2018 received in SEIAA office on 23.05.2018.

With reference to above the proposal has been appraised as per prescribed procedure & provisions under the EIA notification issued by the Ministry of Environment & Forests vide S.O. 1533 (E), dated 14<sup>th</sup> September 2006 and its amendment, on the basis of the mandatory documents enclosed with the application viz., Form I, Form IA, Conceptual Plan, drawings and subsequently submission of PPT & the additional clarifications furnished in response to the observations of the State Expert Appraisal Committee (SEAC) and State Environment Impact Assessment Authority (SEIAA) constituted by the competent Authority.

- i. M/s Man Developments has planned a group housing project "Royal Amar Greens" located at Village- Niranjanpur, District Indore, M.P. Project site is spread over 20350 sq m (5.028 acres) and will have built-up area of 67100.423 sq m.
- ii. The project includes development of residential Complex (Group Housing) (P+6 floor) 10 Blocks.Project comprise of 4 blocks comprising of 11 residential towers, EWS & LIG housing and club along with allied facilities. Till date 6 no. of towers are constructed and built up area of 39843.55 sq. m. is constructed.
- iii. M/s Man Developments has obtained approval from Town and Country Planning (T&CP), M.P. for development of the project in 2011. Due to change in the project planning, layout was revised again in 2016 and approval was taken from the Indore Municipal Corporation (IMC) vide letter dated 15th September, 2016.

Case No. 5689/2018

Issued vide letter no. ..... dated ......

- iv. As per the approval of T & CP Indore (vide L. No. 2344/S.P.604/10/Na. Gra. Ni./2011 dtd 08.04.11) the total land area is 20,350 sq.m.(2.035 ha) at Village –Niranjanpur, Tehsil Indore, Distt. –Indore (M.P.). The total built up area proposed by PP is 45,159.98 sq m. The project comes under 8 (a) category (B) of schedule of EIA Notification, 2006 as the total construction is between 20,000 sqmt. & 1,50,000 sqmt.
- v. The project is a case of violation on account of not securing prior environment clearance before starting the construction activities at site. The construction work was started at site and before the application was submitted to MPSEIAA for grant of prior environmental clearance.
- vi. The Environmental Impact Assessment Notification dated 14th September 2006 as amended to date, states that all project under Item 8(a) shall be appraised as Category B and requires environment clearance from State Environment Impact Assessment Authority. However as the present project is a violation project, it was required to prepare an EIA Report.
- vii. Committee considering the recent Gol, MoEF & CC Notification dated 8th March, 2018 recommends that case may be dealt as per the provisions laid down in this notification and the project may granted Terms of Reference for undertaking Environment Impact Assessment and preparation of Environment Management Plan on assessment of ecological damage, remediation plan and natural and community resource augmentation plan and it shall be prepared as a independent chapter in the EIA report by the accredited consultant and the collection and analysis of data for assessment of ecological damage, preparation of remediation plan and natural and community resource augmentation plan shall be done by an environmental laboratory accredited by the National Accreditation Board for Testing and Calibration Laboratories.
- viii. ToR was granted to the project by SEAC/SEIAA, M.P. vide letter no 207/PS-MS/MPPCB/SEAC/TOR (319)/2018 dated 10/7/2018. EIA for the project was submitted on 24.12.2018. The case was considered in 398<sup>th</sup> SEAC meeting dtd.04.10.2019 and recommended for grant of EC subject special conditions and submission of bank gurantee (BG) with 03 years validity of Rs 30,98,200.00/- (equivalent to amount proposed in remediation and resource augmentation plan) with the MP Pollution control Board.
- ix. PP has submitted the remediation plan and natural community resource augmentation plan corresponding to the ecological damage assessed and economic benefits derived due to violation in the tune of suggested guidelines by the committee, with the supported by documentary proofs, such as bills, CA audit, certificates, photographs, prescribed various undertakings and CER.
- x. PP has proposed Rs. 30,98, 200.00 Lakhs as Remediation Cost and Rs.29,12,000.00 Lakhs as EMP for this project. After recommendation PP has submitted bank guarantee of INR Rs. 30,98,200.00 Lakhs towards Remediation
- xi. Project site belongs to M/s Man Developments through Partner Mr. Rajendra Kumar Mansukhani and M/s Amardeep Builders are developers of the project. Man Developments and Amardeep Builders have entered into a ratio joint development agreement for the development of project. PP has submitted copy of sale deed dtd. 31.03.2010. As per sale deed the said land was purchased by M/s Amardeep Builders.. through Partner Shri Pawan Agrawal. A joint development agreement has been made on 30.03.2011 between M/s Amardeep Builders. through Partner shri Pawan Agrawal and M/s Man Developments through Partner Mr. Rajendra Kumar Mansukhani and Shri Umesh Lilani for development of the project.
- xii. No major source of air pollution during operation phase. A small DG of 250 kVA is provided at the site. This will provide power back-up only for essential utilities like STP, Water supply

- etc. Green area developed is and will properly being maintained and managed. Ambient air quality monitoring will be done every six monthly
- xiii. Total water requirement of the project is estimated to be approx. 330 KLD, out of which domestic water requirement is 315 KLD. Fresh water requirement for the project is approx. 226 KLD (Consumption: 221 KLD, Swimming pool: 5 KLD). Recycled water requirement for the project is 104 KLD (Flushing:94 KLD, Landscaping: 10 KLD). Source of water during operation phase is ground water/Municipal corporation, Indore PP has been taken permission(letter dtd 31.08.15) from District collectorate, Indore for withdrawl of ground water and NOC from IMC (letter dtd.01.06.2015) for water supply.
- xiv. Sewage generation from the project site during operation phase is approx. 271KLD. A STP of 325 KLD is required for treatment of sewage at the site. Dual plumbing system for reusage of STP treated water for flushing and horticulture. It is estimated 216 KLD of water will be recovered after treatment in STP out of which 94 KLD will be used in flushing, 10 KLD in horticulture (Within Site) and 30 KLD Maintaining Park outside the project site. Excess 82 KLD of water is discharged into sewer. This excess water may also be used for green belt along the roads or may be given to nearby construction site for construction purpose. Permission of discharge of excess treated sewage to sewer is granted by Indore Municipal Corporation (letter dtd 14.06.12). STP of 250 KLD is already installed at site and rest 125 KLD STP will be installed in second phase of construction.
- xv. The Municipal Solid Waste approx. 1232 Kg/day, this consist all types of wastes (as recyclable waste 361 Kg/day and non- recyclable waste 871Kg/day) —Generated Solid waste are being segregated & collected and temporarily stored at common solid waste collection center inside the project premises for having a capacity of 48 hour garbage storage, then picked up by hired waste management/ municipal agency for their treatment and disposal. Rejected fraction of the waste is collected and disposed by local agencies on daily basis and will be disposed at the locations designated by Indore Municipal from the project site..
- xvi. Storm water drainage system is provided at project site for channelizing storm water and prevents local flooding. Covered storm water drains are provided at the site. Run-off from the site is collected and recharged into the ground through RWH pits. For rainwater harvesting, 03 recharge pits & 1 tank will be constructed for harvesting rain water.
- xvii. Power requirement for the entire project is 2290 kVA and it will be supplied by Madhya Pradesh State Electricity Board (MPSEB). DG sets of total capacity 250 kVA DG sets are open to air, air cooled & are provided with acoustic enclosure. The proponent has taken various energy conservation measures which include:
  - Energy efficient lifts installed at the site
  - All the electrical fittings and lighting is 5 BEE star rated
  - Usage of low energy embodied locally available construction material. Usage of fly ash bricks, hollow bricks and fly ash mix cement for construction purpose. Usage of excavated soil and construction debris within the project site as filling material
  - Green belt and greenery developed around the project periphery
  - Usage of AAC blocks in building construction
  - Painting wall with white/light colour heat reflecting paint
  - LED lights are used for common area and save 10.5% of energy.
- xviii. Road construction has been undertaken in the project site to facilitate movement of the vehicles expected at the site. Internal roads of adequate width /pedestrian pathways are developed in the project site. Road are designed so as they can bear the expected vehicle load and also width is as per NBC standards for movement of fire tender.

Case No. 5689/2018		
Issued vide letter no	 dated	

- xix. PP has proposed to provide fire fighting provisions with hose reel, hose, wet riser, automatic sprinkler system in entire building, manual call points, automatic fire detection system in entire buildings, underground water storage tank, overhead water tank, fire pumps, potable fire extinguishers, exit signs, P.A. System, Yard Hydrants etc. as per NBC
- xx. Parking facility is provided as per the By Laws of MPBVN. No parking will be done outside the site which will not lead to congestion at entry exit point. Parking space provision for visitors is also kept for the visitors. Roads of adequate width are provided as per MPBVN. PP has proposed total car parking 438 ECS (Basement Parking -196 ECS Stilt Parking-
- xxi. Total area measuring 3280 m2 i.e. 17 % of the net plot area is proposed to be put under green cover. Out of 3280 sq m, approx. 2136 sq m is already developed at the site.
- xxii. PP has proposed to submit bank guarantee of INR 30,98,200.00 towards Remediation Plan and Natural & Community Resource Augmentation Plan with following expenditure:-

Greenery within the	lotal (II	NR) First Year (IN	R) Second Yea	ar Third Year
of the site. No of trees will increased at the site.	for 1500000 acts be	250000	250000	(INR) 1000000
Installation of solar lights with the site for promoting the solar lights within the site energy usage-Provision of 20 no of solar lights within the site  Replacing the single dustbins within the site in color dustbins within the site.	olar 500000	250000		250000
at the site for at source segregation of the waste-11 segregation.	ys   110000 ce ts	55000	_	55000
Provision of signage within the signal of the residents and staff on energonservation, waste management and water conservations	g 50,000 y at	-	***	50,000
mprovement of fire safety signage nd notices in the building fo nhancing awareness on fire azards	50,000	-		50,000
eplacing the CC areas with the avers at site in common areas for shancing the ground water charge (only in non-basement eas)	8,50,000	350000	350000	1,50,000
stallation of fire hooter/alarm in club room as per commendation of SEAC and proving infrastructure for exially abled people in the club of required as per the Fire rms for club room)	40,000			40,000
Total  Ital Project Cost of the project total project As	31,00,000	9,05,000	6,00,000	

i. Total Project Cost of the project is : Rs. 44 Crores Under CER activities PP has proposed cost for the total project As per CER OM, CER cost is 2 % of Rs. 44 Crores, i.e. Rs. 0.88 crores (INR 88 **CER Cost Already Incurred** 

Case No. 5689/2018	
Issued vide letter	
Case No.: To be guoted in	dated
Case No.: To be quoted in register	red cases for correspondence

Activity  Plantation Outside the site (Parallella de la	Cost incurred (INR)
Plantation Outside the site (Development of Municipal Garden)	21,03,580
Development of Cost of Road Outside the project site	33,38,000
Provision of LED on road outside the project site	5,00,000
Landscaping and Maintenance of Sapna Sangeetha Road	13,25,000
Street lights on Sapna Sangeetha Road	5,98,000
Total CER Incurred	78,64,580
Remaining Cost of CSR/CER	9,35,420

### Proposed CER Expenditure:

	Activity	Total Cost (INR)	1st Year	2nd Year	3rd Year
1	Improvement of the Municipal Garden along with provision of garden furniture and development of the walking tracks	9,50,000	3,50,000	3,00,000	3,00,000
	Total	9,50,000	3,50,000	3,00,000	3,00,000

Based on the information submitted at Para i to xx above and others, the State Level Environment Impact Assessment Authority (SEIAA) considered the case in its 644<sup>th</sup> meeting held on 07-10-2020 decided to accept the recommendations of 398<sup>th</sup> dtd. SEAC meeting held on dtd. 04.10.19.

Hence, Environmental Clearance is accorded under the provisions of EIA notification dtd. 14<sup>th</sup> September 2006 and its amendments to the proposed "Group Housing Project "Royal Amar Greens" at Khasra No. 37/1/2, 38/1, 38/2 min 1, 38/2 min 2, 38/2 min 3, 38/2 min 4, 38/2 min 5, 39/1/1, 39/1/2, 39/1/3, 39/2 min 1, 39/2 min 2, 39/2 min 3, 39/2 min 4 and 39/2 min 5 Village Niranjanpur Tehsil Indore District Indore M.P. Total Plot Area: 20350.0 m 2 Net Plot Area: 19405.0 sq.m Built-up Area: 67100.423 sq.m Built-up Area Constructed: 34526.54 sq.m by M/s Man Developments through Partner Mr. Rajendra Kumar Mansukhani G-9, Man Heritage, 6/2 South, Tukoganj, Indore (M.P.) – 452001.

## A. Specific Conditions as recommended by SEIAA:-

- The fresh water supply arrangement should be met through Municipal Corporation Indore
  as per letter dtd.07.05.16 and bore well .PP should explore the possibility to entire
  demand of the water met from the Municipal Corporation Indore.
- 2. The inlet and outlet point of natural drain system should be maintained with adequate size of channel for ensuring unrestricted flow of water.
- 3. Disposal of waste water.
  - a. PP should ensure disposal of waste water arrangement should be done in such a manner that water supply sources are not impaired.
  - PP should explore the possibility to linkage with Nagar Nigam Indore for sewer line for disposal of extra treated waste water.
  - c. The project not having provision for discharge of excess treated sewage cannot permit to start operation unless proper arrangements are put in place for its safe handling.

Case	No.	568	39/2	01	8

### 4. Solid Waste Management:

- a. Separate wet and dry bins must be provided at the ground level for facilitating segregation of waste.
- b. The solid waste generated should be properly collected and segregated. Wet garbage should be composted and dry inert solid waste should be disposed off to the approved sites for land filling after recovering recyclable material.
- c. Ensure linkage with Municipal Corporation, Indore (dtd.03.08.13) for final disposal
- 5. PP should ensure building height, road width, front MOS and side / rear as per approved layout of T & CP.

### 6. For firefighting:-

PP should ensure distance of fire station approachable from the project site & provide fire fighting measures such as water sprinklers, fire hydrant pipe, Adequate firefighting requirement shall be taken into account while designing the electrical distribution system, Wet risers and hose reel, Adequate numbers of fire extinguishers, underground water storage tank properly.

7. For Rain Water Harvesting, and Storm water management:-

PP should ensure the rain water harvesting with 03 recharge pits & 1 tank and these pits should be connected laterally to consume the surplus runoff. In addition, PP should provide recharging trenches. The base of the trenches should be Kachha with pebbles.

8. Car Parking:

PP should ensure to provide car parking 438 ECS (Basement Parking -196 ECS Stilt Parking - 142 ECS . The parking area should not be diverted for any other activities.

### 9. Green belt :-

PP should ensure the area of 3280 m2 i.e. 17 % of the net plot should be developed as greenbelt development with regular maintenance and also explore the possibility to plant trees of indigenous local varieties like Neem, Peepal, Kadam, Karanj, Kachnaar, Saltree, Gulmohar etc.

- 10. PP should ensure to complete the activities listed under ecological remediation, Natural resource augmentation & community resource augmentation for a total amount of Rs. 30, 98, 200.00 PP shall carry out the works assigned under ecological damage, natural resource augmentation and community resource augmentation within a stipulated period and submitted to same in MPSEIAA.
- 11. PP should ensure the implementation of CER activities to the extent of Rs. 9,50,000 (remaining amount of proposed activities) up to three years will be used in Improvement of the Municipal Garden along with provision of garden furniture and development of the walking tracks consultantion with district administration Indore
- 12. PP should ensure to submit half yearly compliance report and CER activity report with photographs of plantation in MP-SEIAA. If PP is failed to upload or submit two consecutive half yearly compliance reports of EC conditions to concerned authority (SEIAA and Regional Office, MoEF&CC,Gol,Bhopal) than prior environmental clearance issued to PP will automatically be treated as cancelled/ revoked as per OM No. 930/SEIAA/2019 dated 30.05.2019 issued by MPSEIAA.

# Specific Conditions as recommended by SEAC

### I. Statutory Compliance

Case No. 5689/2018	
Issued vide letter no dated	
Case No.: To be quoted in registered cases for correspondence	

- i. The project proponent shall obtain all necessary clearance/permission from all relevant agencies including town planning authority before commencement of work. All the construction shall be done in accordance with the local building byelaws.
- ii. The approval of the Competent Authority shall be obtained for structural safety of building due to earthquakes, adequacy of firefighting equipment etc as per National Building code including protection measures from lightening etc.
- iii. The project proponent shall obtain Consent to Establish/Operate under the provisions of Air (Prevention & Control of Pollution) Act, 1981 and the Water (Prevention & Control of Pollution) Act, 1974 from the concerned State Pollution Control Board/Committee.
- iv. The project proponent shall obtain the necessary permission for drawl of ground water/surface water required for the project from the competent authority.
- v. A certificate of adequacy of available power from the agency supplying power to the project along with the load allowed for the project should be obtained.
- vi. All other statutory clearances such as the approvals for storage of diesel from Chief Controller of Explosives, Fire Department, Civil Aviation Department shall be obtained, as applicable, by project proponents from the respective competent authorities.
- vii. The provisions for the solid Waste (Management) Rules, 2016, e-Waste (Management) Rules, 2016, and the Plastics Waste (Management) Rules, 2016 shall be followed.
- viii. The project proponent shall follow the ECBC/ECBC-R prescribed by Bureau of Energy Efficiency, Ministry of Power Strictly.

# II. Air Quality Monitoring and preservation

- Notification GSR 94(E) dated: 25/1/2018 MoEF & CC regarding Mandatory implementation of Dust Mitigation Measures for Construction and Demolition Activities for project requiring Environmental Clearance shall be complied with.
- ii. A management plan shall be drawn up and implemented to contain the current iii. The project propopert shall install the site.
- iii. The project proponent shall install system to carryout Ambient Air Quality monitoring for common/criterion parameters relevant to the main pollutants released covering upwind and downwind directions during the construction period.
- iv. Diesel power generating sets 250 kVA proposed as source of backup power should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use of low sulphur diesel. The location of the DG sets may be decided with in consultation with State Pollution Control Board.
- v. Construction site shall be adequately barricaded before the construction begins. Dust, smoke & other air pollution prevention measures shall be provided for the building as well as the site. These measures shall include screens for the building under construction, continuous dust/ wind breaking wills all around the site plastic/tarpaulin sheet covers shall be provided for vehicles bringing in sand, cement, Murram and other construction materials prone to causing dust polluting at the site as well as taking out debris from the site.
- vi. Sand, Murram, loose soil, cement, stored on site shall be covered adequately so as to prevent dust pollution.
- vii. Wet jet shall be provided for grinding and stone cutting.
- viii. Unpaved surface and loose soil shall be adequately sprinkled with water to suppress dust.
- ix. All construction and demolition debris shall be stored at the site (are not dumped on the roads or open spaces outside) before they are properly disposed. All demolition and construction waste shall be managed as per the provisions of the Construction and Demolition Waste Rules, 2016.

Case No. 5689/2018

Issued vide letter no. ...... dated .........

Case No.: To be quoted in registered cases for correspondence

The diesel generator sets to be used during construction phase shall be low sulphur X. diesel type and shall conform to Environmental (Protection) prescribed for air and noise emission standards.

The gaseous emission from DG set 250 kVA shall be dispersed through adequate XI. stack height as per CPCB standards. Acoustic enclosure shall be provided to the DG sets to mitigate the noise pollution. Low sulphur diesel shall be used. The location of the DG set and exhaust pipe height shall be as per the provisions of the Central Pollution Control Board (CPCB) norms.

For indoor air quality the ventilation provisions as per National Building Code of India.

#### Water quality monitoring and preservation III.

The natural drain system should be maintained for ensuring unrestricted flow of i. water. No construction shall be allowed to obstruct the natural drainage through the site, on wetland and water bodies. Check dams, bio-swales, landscape and other sustainable urban drainage systems (SUDS) are allowed for maintaining the drainage pattern and to harvest rain water.

Buildings shall be designed to follow the natural topography as much as possible

Minimum cutting and filling should be done.

The total water requirement during operation phase is 330 KLD out of which 226 KLD iii. is fresh water requirement and 216 KLD water will be recovered after treatment in STP out of which 94 KLD will be used in flushing, 10 KLD in horticulture within site and 30 KLD uses for maintaining park outside the project site. Excess 82 KLD water will be discharged into municipal sewer. iv.

The quantity of fresh water usage, water recycling and rainwater harvesting shall be to monitor to monitor the water balance as projected by the project proponent. The record shall be submitted to the Regional Office, MoEF & CC along with six monthly

A certificate shall be obtained from the local body supplying water, specifying the total V. annual water availability with the local authority, the quantity of water already committed the quantity of water allotted to the project under consideration and the balance water available. This should be specified separately for separately for ground water and surface water sources, ensuring that there is no impact on other users.

At least 20% of the open spaces as required by the local building bye-laws shall be Vi. previous. Use of Grass pavers, paver blocks with at least 50% opening, landscape

etc. would be considered as previous surface.

Installation of dual pipe plumbing for supplying fresh water for drinking, cooking and Vii. bathing etc and other for supply of recycled water flushing, landscape irrigation, car washing, thermal cooling, conditioning etc. shall be done. viii.

Use of water saving devices/fixtures (Viz. low flow flushing systems; use of low flow faucets tap aerators etc) for water conservation shall be incorporated in the building

Separation of grey and black water should be done by the use of dual plumbing ix. system. In case of single stack system separate recirculation lines for flushing by giving dual plumbing system be done. X.

Water demand during construction should be reduced by use of pre-mixed concrete,

curing agents and other best practices referred.

The local bye-law construction on rain water harvesting should be followed. If local xi. by-law provision is not available, adequate provisions for storage and recharge should be followed as per the Ministry of Urban Development Model Building bylaws, 2016. Rain water harvesting recharge pits/storage tanks shall be provided for ground water recharging as per the CGWB norms.

A rain water harvesting plan needs to be designed where the recharge bores of XII. minimum one recharge bore per 5,000 square meter of built up area and storage capacity of minimum one day of total fires water requirement shall be provided. In areas where ground water recharge is not feasible, the rain water should be

Case No. 5689/2018

Issued vide letter no. ..... dated ......

harvested and stored for reuse. The ground water shall not be withdrawn without

approval from the Competent Authority.

For rainwater harvesting, 3 pits 01 tank recharge pits will be constructed for xiii. harvesting rain water. The total recharge capacity of these pits about 61.06 m3. Mesh will be provided at the roof so that leaves or any other solid waste/debris will be prevented from entering the pit.

The RWH will be initially done only from the roof top. Runoff from green and other xiv.

open areas will be done only after permission from CGWB.

All recharge should be limited to shallow aquifer. XV.

No ground water shall be used during construction phase of the project. XVI.

Any ground water dewatering should be properly managed and shall conform to the xvii. approvals and the guidelines of the CGWA in the matter. Formal approval shall be taken from the CGWA for any ground water abstraction or dewatering.

The quality of fresh water usage, water recycling and rainwater harvesting shall be xviii. measured and recorded to monitor the water balance as projected by the project proponent. The recorded shall be submitted to the Regional Office, MoEF & CC along with six monthly Monitoring report. xix.

Sewage shall be treated in the STP (Capacity - 325 KLD. The treated effluent from STP shall be recycled/re-used for flushing. AC makes up water and gardening.

The waste water generated from the project shall be treated in STP of 325 KLD XX. capacity and then reused for various purposes. No water body or drainage channels are getting affected in the study area because of this project. XXI.

No sewage or untreated effluent water would be discharged through storm water

Periodical monitoring of water quality of treated sewage shall be conducted. xxii. Necessary measures should be made to mitigate the odour problems from STP.

Sludge from the onsite sewage treatment including septic tanks, shall be collected, XXIII. conveyed and disposed as per the Ministry of Urban Development, Control Public Health and Environmental Engineering Organization (CPHEEO) Manual on Sewerage and Sewage Treatment Systems, 2013.

## IV. Noise monitoring and prevention

Ambient noise levels shall conform to residential area/commercial area/industrial area/silence zone both during day and night as per Noise Pollution (Control and Regulation) Rules, 2000. Incremental pollution loads on the ambient air and noise quality shall be closely monitoring during construction phase. Adequate measures shall be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/SPCB.

Noise level survey shall be carried as per the prescribed guidelines and report in this ii. regard shall be submitted to Regional Officer of the Ministry as a part of six-monthly compliance report.

Acoustic enclosures for DG sets, noise barriers for ground run bays, ear plugs for operating personnel shall be implemented as mitigation measures for noise impact due to ground sources.

## V.Energy Conservation measures.

Compliance with the Energy Conservation Building Code (ECBC) of Bureau of Energy Efficiency shall be ensured, Building in the State which have notified their own ECBC, shall comply with the State ECBC.

Outdoor and common area lighting shall be LED.

Energy Conservation Techniques can be considered as Space Cooling: External shading prevents solar radiation from entering into the buildings and reduces the cooling load, results to better control of overheating and indoor temperatures. Space cooling load may be reduced by 30% due to proper shading.

Case No. 5689/2018

Issued vide letter no. ..... dated ......

- iv. Thermal insulation of buildings external walls and roof reduces the cooling load and improves indoor thermal comfort conditions by lowering heat gains through the building's envelope. Energy consumption in insulated buildings may be 5–30% less than in non-insulated buildings.
- v. Domestic hot water: Solar collectors reduce the annual energy consumption for domestic hot water production by lowering the load covered by electrical or thermal heating. Energy consumption in buildings with solar collectors may be 60–80% less than in buildings with electric heaters.
- vi. Concept of passive solar design that minimize energy consumption in buildings by using design elements, such as building orientation, landscaping, efficient building envelope, appropriate fenestration, increased day lighting design and thermal mass etc. shall be incorporated in the building design. Wall, window, and roof u-values shall be as per ECBC specifications.
- vii. Energy conservation measures like installation of CFLs/LED for the lighting the area outside the building should be integral part of the project design and should be in place before project commissioning.

### VI. Waste Management

- Total waste 1232 Kg/day, out of which 361 Kg/day is Recyclable Waste and 871.2 Kg/day is Non Recyclable waste and this shall be treated/ disposed off as per provision made in the MSW Rules 2016.
- ii. A certificate from the competent authority handling municipal solid wastes, indicating the existing civic capacities of handling and their adequacy to cater to the MSW generated from project shall be obtained.
- iii. Disposal of muck during construction phase shall not create any adverse effect on the neighboring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.
- iv. Separate wet and dry bins must be provided in each unit and at the ground level for facilitating segregation of waste. Solid waste (0.4 ton/day) shall be segregated into wet garbage and inert materials.
- v. All non-biodegradable waste shall be handed over the authorized recyclers for which a written lie up must be done with the authorized recyclers.
- vi. Any hazardous waste generated during construction phase, shall be disposed off as per applicable rules and norms with necessary approvals of the State Pollution Control Board.
- vii. Use of environment friendly materials in bricks, blocks and other construction materials, shall be required for at least 20% of the construction materials quantity. These include fly ash brick, hollow bricks, AACs, Fly Ash Lime Gypsum block, compressed earth blocks and other environmental friendly materials.
- viii. Fly ash should be used as building material in the construction as per the provisions of Fly Ash Notification of September, 1999 and amended as on 27th August, 2003 and 25th January, 2016 Ready mixed concrete must be used in building construction.
- ix. Any wastes from construction and demolition activities related thereto small be managed so as to strictly conform to the construction and Demolition Rules, 2016.
- x. Used CFLs and TFLs should be properly collected and disposed off/sent for recycling as per the prevailing guidelines/rules of the regulatory authority to avoid mercury contamination.

### VII. Green Cover

 Total 132 trees shall be planted in the area of 3280 sq.m (17 %) which is developed as greenbelt development out of 3280 sq.m area, 2136 sq.m. is already developed as green belt.

Case No. 5689/2018
Issued vide letter no. ...... dated ...........

- Not tree can be felled/transplant unless exigencies demand. Where absolute necessary, tree felling shall be with prior permission from the concerned regulatory authority. Old trees should be retained based on girth and age regulations as may be prescribed by the Forest Department. Plantations to be ensured species (cut) to
- A minimum of 1 tree for every 80 sqm of land should be planted and maintained. The existing trees will be counted for this purpose. The landscape planning should included plantation of native species. The species with heavy foliage, broad leaves and wide canopy cover are desirable. Water intensive and/or invasive species should not be used for landscaping. iv.
- Where the trees need to be cut with prior permission from the concerned local Authority, Compensatory plantation in the ratio of 1:10 (i.e. planting of 10 trees for every 1 tree that is cut) shall be done and maintained. Plantations to be ensured species (cut) to species (planted). Area for green belt development shall be provided as per the details provided in the project document. V.
- Topsoil should be stripped to depth of 20 cm from the areas proposed for buildings, roads, paved areas, and external services. It should be stack plied appropriately in designated areas and reapplied during plantation of the proposed vegetations on site.

- A comprehensive mobility plan, as per MoUD best practices guidelines (URDPFI), shall be prepared to include motorized, non-motorized, public and private network. Road should be designed with due consideration for environment and safety of users. The road system can be designed with these basic criteria.
  - a. Hierarchy of roads with proper segregation of vehicular and pedestrian traffic

  - c. Proper design of entry and exit points
  - d. Parking norms as per local regulation
- Vehicles hired for bringing construction material to the site should be in good condition and should have a pollution check certificate and should conform to applicable air and noise emission standards be operated only during non-peak hours. iii.
- A detailed traffic management and traffic decongesting plan shall be drawn up to ensure that the current level of service of the road within a 05 Kms radius of the project as maintained and improved upon after the implementation of the project. This plan should be based on cumulative impact of the development and increased habitation being carried out or proposed to be carried out by the project or other agencies in this 05 Kms radius of the site in different scenarios of space and time and the traffic management and the PWD/competent authority for road augmentation and shall also have their consent to the implementation of components of the plan which involve the participation of these departments.

#### IX. Human health issues

- All workers working at the construction site and involved in loading, unloading, carriage of construction material and construction debris or working in any area with dust pollution shall be provided with dust mask. ii.
- For indoor air quality the ventilation provisions as per National Building Code of India.
- Emergency preparedness plan based on the Hazard identification and Risk iii. Assessment (HIRA) and Disaster Management Plan shall be implementation. iv.
- Provision shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile, STP, safe drinking water, medical health care, crèche etc. The housing may be in the form of temporary structures to be removed after the completion of the project.
- Occupational health surveillance of the workers shall be done on a regular basis.

Case No. 5689/2018 Issued vide letter no. ..... dated ...... Case No.: To be quoted in registered cases for correspondence

A First Aid Room shall be provided in the project both during construction and vi. operations of the project.

#### X. Corporation Environment Responsibility

The project proponent shall comply with the provisions contained in this Ministry's OM vide F.No. 22-65/2017-IA.III dated: 1st May 2018, as applicable, regarding Corporate

Environment Responsibility.

The company shall have a well laid down environmental policy duly approved by the Board of Directors. The Environmental policy should prescribe for standard operating procedures to have proper checks and balance and to bring into focus any infringements/deviation/violation of the environmental/forest/wildlife norms/conditions. The company shall have defined system of reporting infringements/deviation/violation of the Environmental/forest/wildlife norms/conditions and/or shareholders/stake holders. The copy of the board resolution in this regard shall be submitted to the MoEF&CC as a part of six monthly reports.

A separate Environmental Cell both at the project and company head quarter with qualified personnel shall be set up under the control of senior Executive, who will

directly to the head of the organization.

Action plan for implementing EMP and environmental conditions along with iv. responsibility matrix of the company shall be prepared and shall be duly approved by competent authority. The year wise funds earmarked for environmental protection measures shall be kept in separate account and not to be diverted for any other purpose. Year wise progress of implementation of action plan shall be reported to the Ministry/Regional Office along with the Six Monthly Compliance Report.

PP has proposed Rs. 23,20,000.00 Lakhs capital cost and Rs. 5,92,000 Lakh as

recurring cost for EMP of this project

For this project PP has proposed total cost for CER Rs. 9.50 Lakh as capital in which is vi. @ Rs. 3.50 lakhs/year amount shall be disbursed in the three years as recurring.

#### XI. Miscellaneous

The project authorities must strictly adhere to the stipulation made by the MP i. Pollution Control Board and the State Government.

The project proponent shall abide by all the commitments and recommendations ii. made in the EIA/EMP report, commitment made during Public Hearing and also that during their presentation to the State Expert Appraisal Committee (SEAC)

No further expansion or modification in the plant shall be carried out without prior iii. approval of the Ministry of Environment, Forests and Climate Change (MoEF&CC).

Concealing factual data or submission of false/fabricated data may result in iv. revocation of this environmental clearance and attract action under the provisions of Environment (Protection) Act, 1986.

The above conditions shall be enforced, inter-alia under the provisions of the Water (Prevention & Control of Pollution) Act, 1974, the Air (Prevention & Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986, Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016 and the Public Liability Insurance Act, 1991 along with their amendments and Rules and any other orders passed by the Hon'ble Supreme Court of India/High Courts and any other Court of Law relating to the subject matter.

### Standard Conditions:

1. All activities / mitigative measures proposed by PP in Environmental Impact Assessment (if applicable) and approved by SEAC must be ensured.

Case No. 5689/2018

Issued vide letter no. ..... dated ......

- All activities / mitigative measures proposed by PP in Environmental Management Plan and approved by SEAC must be ensured.
- Project Proponent has to strictly follow the direction/guidelines issued by MoEF, CPCB and other Govt. agencies from time to time.
- The Ministry or any other competent authority may alter/modify the conditions or stipulate any further condition in the interest of environment protection.
- The Environmental Clearance shall be valid for a period of seven years from the date of issue of this letter.
- 6. The Project Proponent has to upload soft copy of half yearly compliance report of the stipulated prior environmental clearance terms and conditions on 1st June and 1st December of each calendar year on MoEF & CC web portal http://www.environmentclearance.nic.in/ or http://www.efclearance.nic.in/ and submit hard copy of compliance report of the stipulated prior environmental clearance terms and conditions to the Regulatory Authority also
- 7. The Regional Office, MoEF, Gol, Bhopal and MPPCB shall monitor compliance of the stipulated conditions. A complete set of documents including Environment Impact Assessment Report. Environmental Management Plan and other documents information should be given to Regional Office of the MoEF, Gol at Bhopal and MPPCB.
- The Project Proponent shall inform to the Regional Office, MoEF, Gol, Bhopal and MP PCB regarding date of financial closures and final approval of the project by the concerned authorities and the date of start of land development work.
- In the case of expansion or any change(s) in the scope of the project, the project shall again require prior Environmental Clearance as per EIA notification, 2006.
- 10. The SEIAA of M.P. reserves the right to add additional safeguard measures subsequently, if found necessary, and to take action including revoking of the environment clearance under the provisions of the Environmental (Protection) Act, time bound and satisfactory manner.
- 11. All other statutory clearances such as the approvals for storage of diesel from Chief Controller of Explosives, Fire Department, Civil Aviation Department, Forest Conservation Act, 1980 and Wildlife (Protection) Act, 1972 etc. shall be obtained (as authorities.
- 12. The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM, SO2, NOx (ambient levels as well as stack emissions) or critical sectoral parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company and in the public domain.
- 13. Any change in the correspondence address be duly intimated to all the regulatory authority within 30 days of such change.

- 14. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the Regional Office of MoEF
- 15. A copy of the environmental clearance shall be submitted by the Project Proponent to the Heads of the Local Bodies, Panchayat and municipal bodies as applicable in addition to the relevant officers of the Government who in turn has to display the same for 30 days from the date of receipt.
- 16. The Project Proponent shall advertise at least in two local newspapers widely circulated, one of which shall be in the vernacular language of the locality concerned, within 7 days of the issue of the clearance letter informing that the project has been accorded environmental clearance and a copy of the clearance letter is available with the State Pollution Control Board and also at website of the State Level Environment Impact Assessment Authority (SEIAA) at www.mpseiaa.nic.in and a copy of the same shall be forwarded to the Regional Office, MoEF, Gol, Bhopal.
- 17. Any appeal against this prior environmental clearance shall lie with the Green Tribunal, if necessary, within a period of 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.

Dated 29:10: 25

(Tanvi Sundrival) Member Secretary

Endt No. Copy to:-

1. Principal Secretary, Urban Development & Environment Deptt. 3rd Floor, Mantralaya Vallabh Bhawan, Bhopal.

2. Secretary, SEAC, Research and Development Wing Madhya Pradesh Pollution Control Board, Paryavaran Parisar, E-5, Arera Colony Bhopal-462016.

3. Member Secretary, Madhya Pradesh Pollution Control Board, Paryavaran Parisar, E-5, Arera Colony, Bhopal-462016.

4. The Collector, District Indore, M.P.

5. The Commissioner, Municipal Corporation, Indore, MP

6. The Town & Country Planning District Office, Indore MP

7. Director, I.A. Division, Monitoring Cell, MoEF, Gol, Ministry of Environment & Forest Indira Paryavaran Bhawan, Jor Bagh Road, New Delhi - 110 003

8. Director, I.A. Division, Monitoring Cell, MoEF, Gol, Ministry of Environment & Forest Indira Paryavaran Bhawan, Jor Bagh Road, New Delhi - 110 003

9. Director (S), Regional office of the MOEF, (Western Region), Kendriya Paryavaran Bhawan, Link Road No. 3, Ravi Shankar Nagar, Bhopal-462016.

10. Guard file.

(Dr. Sameev Sachdev) Officer-in-Charge

Case No. 5689/2018

Issued vide letter no. ..... dated ......